

15-147-00013-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

Well Location CE 1/2 SE SE Sec. 6 Twp. 4 Rge. (E) (W) 17

Field Name (if any) None County Phillips

Lease (Farm Name) Lloyd Loyd Well No. 1

Was well log filed with application? Yes If not, explain circumstances and give available data (Use an additional sheet if necessary)

Well plugged on verbal authorization C.T. Alexander

Date and hour plugging is desired to begin 8:00 A.M. 6-13-41

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desires (Use an additional sheet if necessary) No exception

Name of the person on the lease in charge of well for owner

C. R. Smith Address Russell, Kansas.


Name of well owner or Acting Agent Helmerich & Payne, Inc. et al

Address 415 Philtower, Tulsa, Oklahoma.

Invoice covering assessment for plugging this well should be sent to:

Helmerich & Payne, Inc. Address Tulsa, Oklahoma.

and payment will be guaranteed by applicant.



PLUGGING
FILE 6 4-R17K
BOOK PAGE 141 LINE 29

C. M. Copeland
Operator or Acting Agent

Date 6-17-41

13-147-0003-00-00

Loyd #1
SE of Section 6-4S-17W
Phillips County, Kansas
W. C. Jackson - F. L. Feaster
and
Helmerich & Payne, Inc.

Commenced: May 30, 1941
Completed: June 18, 1941

Surface clay	0	130
Shale and lime	130	180
Shale and shells	180	600
Sand and shale	600	710
Sand	710	745
Shale, sand and shells	745	930
Sand	930	1130
Lime and shale	1130	1200
Sand	1200	1360
Shale and sand	1360	1420
Red bed	1420	1430
Shale	1430	1640
Lime	1640	1665
Shale and lime	1665	1860
Broken lime	1860	1960
Broken lime	1960	2265
Lime and shale	2265	2360
Lime and shale	2360	2380
Lime	2380	2410
Broken lime	2410	2420
Lime and shale	2420	2495
Lime, broken	2495	2620
Broken lime and shale	2620	2740
Shale and shells	2740	2778
Lime	2778	2860
Broken lime	2860	2894
Lime	2894	3220
Broken lime	3220	3295
Lime	3295	3331
Lime and shale	3331	3385
Lime	3385	3460
Broken lime	3460	3578
Shale, lime and chert	3578	3620
Broken lime	3620	3642
Shale and lime	3642	3680
Arbuskila lime (top)	3680	3687
Lime	3687	3715
Broken lime	3715	3765
Lime	3765	3820
TOTAL DEPTH		3820

PLUGGING RECORD

Drove wood plug to 180'. Filled with 1/2 yard chat. Pumped 15 sacks of cement on chat. Made cement plug at top of surface pipe with 5 sacks of cement.

PLUGGING
6 # 2 1/2 W
300' 6-14 LINE 29

STATE OF OKLAHOMA)
) ss
COUNTY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Loyd Well #1, located in the Southeast Quarter of Section 6, Township 4 South, Range 17 West, Phillips County, Kansas.

HELMERICH & PAYNE, INC.
By William Broad
Treasurer

Subscribed and sworn to before me, a Notary Public, this 18th day of June, 1941.

Lee Griffin
Notary Public

My commission expires July 22, 1943.

6-18-41



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

June 14, 1941

IN REPLY PLEASE
REFER TO THIS
SUBJECT

15-147-00013-00-00

Well No. 1
Farm ~~Lloyd~~ Lloyd
Description C E $\frac{1}{2}$ SE SE 6-4-17W
County Phillips
File 141-28

Helmerich & Payne, Inc.
415 Philtower Bldg.
Tulsa, Oklahoma

Dear Sirs:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

HA

BY: J. P. Roberts
J. P. ROBERTS

NOTICE: C. T. Alexander
Great Bend, Kansas