

RECEIVED

OCT 11 2002

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-147-30083-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Jason Bach dba Bach Oil Production, Inc. KCC LICENSE # 31569  
(owner/company name) (operator's)

ADDRESS P.O. Box 723 CITY Alma

STATE Nebraska ZIP CODE 68920 CONTACT PHONE #(308) 928-2221

LEASE Quanz A WELL# 1 SEC. 29 T. 04S R. 18 (xxxx/West)

- N/2- SE - NE SPOT LOCATION/QOOO COUNTY Phillips

3630 FEET (in exact footage) FROM S/x (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/x (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL x GAS WELL     D&A     SWD/ENHR WELL     DOCKET#    

CONDUCTOR CASING SIZE     SET AT     CEMENTED WITH     SACKS

SURFACE CASING SIZE 8-5/8 SET AT 198' CEMENTED WITH 140 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3312' CEMENTED WITH 250 SACKS  
Squeezed from 880'-1990' with 350 sx. Cement.

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3093-04; 3152-59; 3169-76; 3188-94; 3245-51; 3262-68; 3009-11. BP @ 3220'

ELEVATION 1893 KB T.D. 3335' PBDT 3185' ANHYDRITE DEPTH 1427'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD x POOR     CASING LEAK     JUNK IN HOLE    

PROPOSED METHOD OF PLUGGING Run tubing to 1900' Spot 50 SX 60-40 Poz +10 % gel + 4 sx hulls. Pull to 950' Circulate 50 sx 60-40- Poz +10% gel to surface. Pull Tubing And squeeze @ surface as needed. Plug 8-5/8 - 4-1/2 annulus w/ 25 sx 60/40 Poz + 10% gel w/ 2 sx hulls.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? NO  
(Log sent with earlier application)  
If not explain why? No ACO-1 in 1965

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

GARY L. REED PHONE# (316) 733-4798

ADDRESS 14200 BROOKLINE CT. City/State WICHITA, KANSAS 67230

PLUGGING CONTRACTOR Allied Cementing Co., Inc. KCC LICENSE # 99994  
(company name) (contractor's)

ADDRESS PO BOX 31 Russell, KS 67665-0031 PHONE # (785) 483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) As Soon as possible

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR XXXXXXXX

DATE: 10/09/02 AUTHORIZED OPERATOR/AGENT: Gary L Reed  
(signature)



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Bach, Jason dba Bach Oil Production  
RR 1, Box 28  
Phillipsburg, KS 67661

October 15, 2002

Re: QUANZ A #1  
API 15-147-30083-00-00  
N2SENE 29-4S-18W, 3630 FSL 660 FEL  
PHILLIPS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely  
  
David P. Williams  
Production Supervisor