

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1985

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

6-19-85

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-147-20,262-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Terra Resources, Inc. OPERATORS LICENSE NO. 7368

ADDRESS P. O. Box 839, Oklahoma City, OK 73101 PHONE # (405) 840-5590

LEASE (FARM) McCamish WELL NO. 1 WELL LOCATION C NE NE COUNTY Phillips

SEC. 27 TWP. 4S RGE. 18 (~~E)X(W)) TOTAL DEPTH 3656 PLUG BACK TD 3346~~

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 578 CEMENTED WITH 300 SACKS

CASING SIZE 5 1/2 SET AT 3388 CEMENTED WITH 225 SACKS

PERFORATED AT 3260-78'; 3129-34'; 3055-61'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump into 5 1/2" casing with 75 sacks

60/40 Pozmix with 10% gel + 3% cc and 2 sx hulls followed by 28 sx gel in water followed by

50 sx 60/40 Pozmix with 10% gel + 3% cc followed by 8 sx gel in water. Release 5 1/2" wiper.
(If additional space is needed use back of form) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 8:00 a.m. 7/15/85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wayne Dolezal PHONE # (913) 483-2331

ADDRESS Route 1, Russell, KS 67665

PLUGGING CONTRACTOR Not yet assigned LICENSE NO. _____

ADDRESS _____ PHONE # _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: 6/25/85

plug followed by 58 sx 60/40 Pozmix with 10% gel and 3% cc. Tie onto 8 5/8" and 5 1/2" annulus. Pump 200 sx 60/40 Pozmix with 10% gel and 3% cc. Cut off casing 4' below ground level and weld on cap.