

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

API NUMBER 15-147-20,339 -00-00 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER Viking Energy Management

ADDRESS 2761 E. Skelly Dr., Tulsa, OK 74105

LEASE (FARM NAME) E.E. QUANZ WELL NO. 1

WELL LOCATION C E/2 E/2 SE NW SEC. 26 TWP. 4S RGE. 18W (EAST) (WEST)

COUNTY Phillips TOTAL DEPTH 3265' FIELD NAME _____

OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A XX

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? YES
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 2:35 p.m., 8/11/81.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wilmer Dreiling (Toolpusher) ADDRESS 408 Jefferson, Ellis, Kansas 67637

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. _____

ADDRESS 801 Union Center, Wichita, KS 67202

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Viking Energy Management Co.

ADDRESS 2761 E. Skelly Drive, Tulsa, OK 74105

RECEIVED
STATE CORPORATION COMMISSION

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OF ACTING AGENT.

SIGNED: Jack L. Partridge

CONSERVATION DIVISION
Wichita, Kansas
APPLICANT OR ACTING AGENT
Jack L. Partridge, Vice President

DATE: August 13, 1981

AUG 14 1981

8-14-81

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

September 28, 1981

INVOICE NUMBER: 7725-W

TO: Viking Energy Management Co.
2761 East Skelly
Tulsa, OK., 74105

15-147-20339-00-00

PLUGGING ASSESSMENT AS FOLLOWS:

PAYABLE UPON RECEIPT

Quanz #1
C E $\frac{1}{2}$ SE NW +200' SW m Sec.26-4S-18W
Phillips

NOTE: We also need the following before our file is completed: ^{3265'} \$106.11

- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

Albert J. Costa
For Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS., 67601

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE

CONTRACTORS WELL LOG

15-147-20339-00-00

OPERATOR: Viking Energy Management Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: E.E. QUANZ #1
 LOCATION: C E/2 E/2 SE NW, Sec. 26-4S-18W
 Phillips County, Kansas
 SPUD DATE: 8/04/81
 COMPLETION DATE: 8/11/81

0	380	Shale
380	1816	Sand & Shale
1816	2799	Shale
2799	2944	Shale & Lime
2944	3030	Shale
3030	3060	Lime
3060	3135	Shale & Lime
3135	3265	Lime
	3265	Rotary Total Depth

Spud hole @ 1:15 a.m., 8/04/81. Drilled 1004' of a 12 1/4" hole. Ran 24 joints of 8 5/8" 23# casing set @ 1003' and cemented with 250 sx. of 60-40 posmix, 2% gel, 3% c.c. Followed with 250 sx. common 2% gel, 3% c.c. Plug was down @ 6:00 a.m., 8/05/81.

3625' TD. Set 1st plug @ 990' with 80 sx. Set 2nd plug @ 270' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole, 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 2:35 p.m., 8/11/81.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the E.E. QUANZ #1, C E/2 E/2 SE NW, Sec. 26-4S-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 13th day of August, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION

AUG 14 1981

CONSERVATION DIVISION
 Wichita, Kansas

8-14-81

