

KANSAS

Form CP-3  
Rev. 6-4-68

*R*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 16 1976

*8-16-76*

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 147-30089-00-00 (of this well)

Operator's Full Name Petroleum Management, Inc.

Complete Address P.O. Box 1325, Great Bend, Kansas 67530

Lease Name Barney Morgan Well No. 2

Location SE NW SW Sec. 21 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3330'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Bpx 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12 N Day 13 Month 8 Year 1976

The above well was plugged as follows:

Total Depth 3330' 8 5/8 csg set 220' cwc 160 sk.

4 1/2 csg set 3329' cw 150 sx cem.

4 1/2 csg PBTB 3290' & top perf. (3166'-3170')

Set 4 1/2 wood plug at 3110' -poured 10' sd -dumped 3 sk cem W/dump bailer. (3110'-3070')

Cutoff & recovered 1415' of 4 1/2 csg.

Hallib. Cem. Co. squeezed 8 5/8 csg with 25 sk gel & water W/100 lbs hulls -  
released 8 5/8 plug & pumped 125 sx cem. (Halco-Light)

I hereby certify that the above well was plugged as herein stated.

Signed: *Reo Marnoff*  
Well Plugging Supervisor

**INVOICED**

DATE 8/16/76  
INV. NO. 3631-W