

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 - 1971  
CONSERVATION DIVISION  
Wichita, Kansas

7-9-71

15-147-30087-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Inc.

Complete Address 1515 Vickers KSB & T Bldg., Wichita, Kansas 67202

Lease Name B. Morgan Well No. 3

Location C SE NW Sec. 21 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3375'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 2:15 P Day 8 Month 7 Year 1971

The above well was plugged as follows:

Total Depth 3375' 8 5/8 csg set at 220' cwc 140 sk.

4 1/2 csg set at 3373' cw 150 sk cmt.

4 1/2 csg perf. (3137-3140)

Pumped 30 sk cmt plug (3000-3220)

Cutoff and recovered 1243' of 4 1/2 csg.

Pumped down 8 5/8 csg with 18 sk gel W/3 sk hulls -70 sk poz 6% -7 sk gel -release

plug and pumped 50 sk poz 6%. Max pres. 600 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 7-9-71

INV. NO. 3959-W