

GR

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-30139-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 - 1971

CONSERVATION DIVISION
Wichita, Kansas

17-6-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Incorporated,

Complete Address P. O. Box #922, Great Bend, Kansas.

Lease Name Sutley Well No. 7

Location NE-SW-NW Sec. 29 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3380'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 8:00 PM Day 2 Month 7 Year 1971

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 140 Sx.
3272'--4 1/2" Production casing cemented on bottom with 250 Sx. Top perforations from
3042' to 3048'.

Pushed plug to 3000', sanded well back to 2975' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 4 sacks hulls and 14 sacks gelat
then 15 Sx. cement from 750' to 375' then 3 sacks gel from 375' to 225' and followed
with 1 sack hulls and 25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to
30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in press-
ure-300#. Final shut-in pressure-50#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7-7-71
INV. NO. 3944-W