

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-197-30138-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1968
CONSERVATION DIVISION
Wichita, Kansas
1-29-68

Operator's Full Name James W. Hershberger

Complete Address 807 1st Nat'l Bk. Bldg., Wichita, Ks

Lease Name Bredemeir Well No. 4

Location C NE NW Sec. 28 Twp. 4 Rge. 18 (E) (W) X

County Phillips Total Depth 3350'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Santa Fe Pipe & Supply

Address Box 562 Great Bend, Ks. License No. 574

Operation Completed: Hour 11:15 A Day 25 Month 1 Year 1968

The above well was plugged as follows:

Total Depth 3350' 8 5/8 csg set at 202' cwc 140 sc.

4 1/2 csg set at 3339' cw 250 sc cement.

4 1/2 csg perf. (3178-82)

Filled with sand to 3100' and dumped 4 sc cement with dump bailer.

Recov. 1208' of 4 1/2 csg.

Squeezed thru 8 5/8 plg container W/ 30 sc gelW/5 hulls, Plg and 140 sc cement.

Cementing material 140 sc of 50-50 poz cement W/6% gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 1/29/68

INV. NO. 7167-u