

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-20-78
MAR 20 1978
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 147-30088-00-00

Operator's Full Name Petroleum Management, Inc.

Complete Address 400 North Woodlawn-Suite 201, Wichita, Kansas 208

Lease Name Barney Morgan Well No. 1

Location NW NW SW Sec. 21 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3510'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Co. Tools

Address _____ License No. 731

Operation Completed: Hour 3:30 P Day 16 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 3510' 8 5/8 csg set 193' cwc

4 1/2 csg set 3413' cw 150 sk cem.

4 1/2 csg Perf. (3116'-3120')

Filled 4 1/2 csg with sand (3510'-3100') dumped 3 sk cem. W/dump bailer. (3100'-3270')

Cutoff & recovered 750' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water

with 100 lbs hulls, released cementing plug & pumped 140 sk cem & shutin. # 350lbs.

FPP

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-21-78
NO. 6939-W