

200 PA

Form CP-3  
Rev. 6-4-68

K

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 16 1976  
8-16-76

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -147-30137-0-09 (of this well)

Operator's Full Name Petroleum Management, Inc.

Complete Address P.O. Box 1325, Great Bend, Kansas 67530

Lease Name Barney Morgan Well No. 5

Location SW SW Sec. 21 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3342'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:30 A Day 13 Month 8 Year 1976

The above well was plugged as follows:

Total Depth 3342' 8 5/8 csg set 190' ~~csg~~ ~~225'~~ cwc 140 sk.

4 1/2 csg set 3341' cw 250 sx cem.

4 1/2 csg PBTB 3297' with top perf. (3090-3092)

Set 4 1/2 wood plug at 3010' -poured 10' sd -dumped 3 sx cem W/dump bailer. (3010-2970)

Cutoff & recovered 70 jts. (2215') of 4 1/2 csg.

Halliburton Cementing Co. squeezed 8 5/8 csg with 25 sk gel & water W/100 lbs

hulls -released 8 5/8 plug & 125 sk cem. (Halco-Light)

I hereby certify that the above well was plugged as herein stated.

Signed: B. M. Manner  
Well Plugging Supervisor

INVOICED

DATE 8/16/76

INV. NO. 3630-W