

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1976

8-16-76

CONSERVATION DIVISION
Wichita, Kansas

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 147-20035-00-00 (of this well)

Operator's Full Name Petroleum Management, Inc.

Complete Address P. O. Box 1325, Great Bend, Kansas 67530

Lease Name Barney Morgan Well No. 6

Location C SW NW Sec. 21 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3340'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2 P Day 13 Month 8 Year 1976

The above well was plugged as follows:

Total Depth 3340' 8 5/8 csg set 202' cwc 160 sx.

4 1/2 csg set 3339' cw 250 sx cem.

4 1/2 csg PBTD 3316' with top perf. (3188'-3194')

Set 4 1/2 wood plug at 1600' - poured 10' sd -dumped 3 sk cem W/dump bailer. ((1600-1550))

Cutoff & recovered 12 jts (384') of 4 1/2 csg.

Hallib. Cem. Co. squeezed 8 5/8 csg with 20 sk gel & water W/100 lbs hulls -

released 8 5/8 plug & 100 sk cem. (Halco-Light)

I hereby certify that the above well was plugged as herein stated.

Signed: Bob Massey
Well Plugging Supervisor

INVOICED

DATE 8/16/76

INV. NO. 3629W