

*P*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-30118-00-~~00~~  
01

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
2-19-68

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Management, Inc.

Complete Address: 1515 Wichita Plaza Wichita, Ks. 67202

Lease Name Barney Morgan Well No. 4

Location N/2 NE SE Sec. 21 Twp. 4 Rge. 18 (E) (W)

County Phillips Total Depth 3480

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knights Casing Pulling Co.

Address: Box 4055 Chase, Ks. License No. 436

Operation Completed: Hour 12 N Day 15 Month 2 Year 1968

The Above well was plugged as follows:

Total Depth 3480' 8 5/8 csg set at 220' cwc 160 sc.

4 1/2 csg set at 3480' cw 250 sc cement.

PBTD 3330' with top perf at 3088'.

Sanded back to 3000' and dumped 4 sc cement with dump bailer.

Recov. 1475' of 4 1/2 csg.

Pumped thru 8 5/8 in plg container W/30 sc gel, plg and 140 sc cement W/6% total gel.

Pumping pres. 150 lbs. Shutin Pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. F. Massey  
Well Plugging Supervisor

DATE 2/19/68

INV. NO. 7288-11