

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 - 1971  
CONSERVATION DIVISION  
Wichita, Kansas

15-147-30124-00-01

Operator's Full Name Petroleum Management, Inc.

Complete Address 1515 Vickers KSB & T Bldg., Wichita, Kansas 67202

Lease Name Quanz "A" Well No. 3

Location S/2 NE SE Sec. 29 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3270'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 4:15 P Day 8 Month 7 Year 1971

The above well was plugged as follows:

Total Depth 3270' 8 5/8 csg set at 198' cwc 140 sk.

4 1/2 csg set at 3264' cw 250 sk cmt.

4 1/2 csg perf. (3044-3205)

Pumped 30 sk cmt plug to 2900'.

Cutoff and recovered 769' of 4 1/2 csg.

Pumped down 8 5/8 csg with 18 sk gel W/3 sk hulls, -70 sk poz 6%, -7 sk gel, -release

plug and pumped 50 sk poz 6%. Max. pres. 300 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Manning  
Well Plugging Supervisor

DATE 7-9-71

INV. NO. 3960-W