

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 147-20,238-00 (of 10 Wells, Kansas)

RECEIVED
STATE CORPORATION COMMISSION
7-23-80
JUL 23 1980
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name KANSAS OIL CORPORATION

Complete Address 400 NORTH WOODLAWN - WICHITA, KS. 67208

Lease Name FERGUSON Well No. #3

Location NW-SE-SE Sec 34 Twp. 4 Rge. 18 (E) (W) W

County PHILLIPS Total Depth 3453 ^{FE}

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor MIDWEST CASING PULLING

Address BOX F. SUBLETTE, MS. 67877 License No. 766

Operation Completed: Hour 4:20 PM Day 22 ND Month JULY Year 1980

The above well was plugged as follows:

8 5/8" 252 FE SD. CUC. w/ 165 SE OMT. -> 4 1/2" SET AT 3453 FE.

PERF'S - 3142' - 46' -> SQUEEZED AT 1300 FE w/ 175 SE OMT.

NO PIPE RECOVERY.

ORDERED 150 SE 50% Pozmix 6% GEL. -> 12 SE GEL. + 4 SE HULL'S

PUMPED IN WITH PUMP TRUCK.

PUT 8 SE OMT + 2 HULL IN ANNULUS. MAX PRESSURE 900 LBS.

PUT IN 4 1/2" - 2 SE HULL'S -> 35 SE OMT. -> 12 SE GEL. -> 1 SE HULL'S

AND 25 SE OMT. MAX PRESSURE - 2000 LBS SHUT IN 1700 LBS

(CEMENTED BY ALLIED OMC)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Marvin Schmidt
Well Plugging Supervisor

DATE 7-23-80

W. NO. 2675-W