

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: K & N Petroleum  
Address: 513 West 6th Street, Ellinwood, Kansas 67526  
Phone: (620) 564-3422 Operator License #: 3208  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) 7/13 (If SWD or ENHR)  
The plugging proposal was approved on: September 8th, 2004 (Date)  
by: Jack Luthi (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 3078' Bottom: 3317' T.D. 3325'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-159-20,186-00-00  
Lease Name: Mansz  
Well Number: #3-D <sup>KCC</sup> BEM 9-24-04  
Spot Location (QQQQ): <sup>30' W of SE</sup> - NE - NE - \_\_\_\_\_  
990' Feet from  North /  South Section Line  
330' Feet from  East /  West Section Line  
Sec. 17 Twp. 19 S. R. 10  East  West  
County: Rice  
Date Well Completed: 2/27/1969  
12/10/1968 <sup>KCC</sup>  
Plugging Commenced: 9/9/04 <sup>BEM</sup>  
Plugging Completed: 9/16/04 <sup>9-24-04</sup>

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	215'	8-5/8"	215'	0'
	Production	0'	3319'	5-1/2"	3319'	1596.97'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Spot sand trailer in. Spot sand to 3028'. Got 45 bbls. in hole with water truck - let fall. Spot 5 sx cement on top of sand. Set jacks - no casing equipment for tongs to tighten lift sub. Hooked up knife. Put tongs together - pulled slips with jacks - broke head off - pulled stretch on 5-1/2". Worked casing for awhile - 5-1/2" stretch. Pulled stretch. Trip in hole - cut pipe. Pulled to 1300'. Pumped 100# hulls and 35 sx cement. Pulled to 850' - pumped 50# - pulled to 265' - circulated to surface. Trip out of hole with rest of pipe. Tore down equipment - rigged down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901


Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: K & N Petroleum

State of Kansas County, Barton, ss.

Edward S. Nennich (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 **KAREN J. MITCHELL**  
Notary Public - State of Kansas  
My Appt. Expires 4/13/06

(Signature) Edward S. Nennich

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 21st day of September, 20 04

  
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
SEP 23 2004  
KCC WICHITA