

ATE CORPORATION COMMISSION
3 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-155-20125-00-02

LEASE NAME Dion #1

WELL NUMBER #1

2310 Ft. from S Section Line

990 Ft. from ^W Section Line

SEC. 3 TWP. 23S RGE. 10W (X) or (W)

COUNTY Reno

Date Well Completed 12-20-02
7/10/99

Plugging Commenced 7/15/04

Plugging Completed 7/19/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR WHITETAIL CRUDE, INC

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well Gas Oil

Well (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/14/04

Mike Wilson (KCC District Agent's Name)

ACO-1 filed? yes If not, is well log attached? no

Producing Formation Lansing Depth to Top _____ Bottom _____ T.D. PBTD 3320

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>4 1/2</u>	<u>3770</u>	<u>1420</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material is used, state the character of same and depth placed, from _____ feet to _____ feet each set.
7/15/04 Tried to cover bottom perfs by dumping sand, ran dump bailer to spot cement on top of sand, pulled dump bailer & well started to flow, called KCC For instructions. 7/16/04 Spotted 150 more scoops of sand, ran depthometer & found sand plug @ 3025'. Dumped 4 sks cement via dump bailer. 7/19/04 Shot pipe off @ 1420', pulled 1 jt, pumped 35 sk plug, pulled casing to 911', pumped another 35 sk plug, pulled casing to 300', pumped cement to surface, pulled casing out, topped off 8 5/8, Job complete.

Name of Plugging Contractor Whitetail Crude, Inc License No. 31627

Address P O Box 544, Ness City, KS 67560-0544

RECEIVED

Name of Party Responsible for Plugging Fees: Whitetail Crude, Inc

SEP 02 2004

State of Kansas County of Ness, ss.


KCC WICHITA

Mike J. Fritzler, President Whitetail Crude, Inc (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 1st day of September, 2004, at _____



Debra Kerr Notary Public

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM

DM



POST OFFICE BOX 438
 HAYSVILLE, KS 67060
 (316) 524-1225
 (316) 524-1027 FAX

INVOICE

BURRTON, KS
 (620) 463-5161
 FAX (620) 463-2104

GREAT BEND, KS
 (620) 793-3366
 FAX (620) 793-3536

INVOICE NUMBER

0024937-IN

BILL TO: MIKE FRITZLER TRUCKING INC
 BOX 444
 NESS CITY KS 67560

LEASE: DION 1

Mike J Fritzler

DATE	ORDER	SALESMAN	ORDER DATE	PURCHASE ORDER	SPECIAL INSTRUCTIONS
07/22/04	24937		07/19/04		

QUANTITY	U/M	ITEM NO/DESCRIPTION	D/C	PRICE	EXTENSION
1.00	EA	PUMP TRUCK SQUEEZE	.00%	400.00	400.00
51.00	MI	PUMP TRUCK MILEAGE	.00%	2.50	127.50
250.00	SAX	60-40 4% POZ	.00%	6.00	1,500.00
5.00	SK	GEL	.00%	9.50	47.50
250.00	EA	BULK CHARGE	.00%	1.00	250.00
561.00	MI	BULK TRUCK - TON MILES	.00%	.85	476.85
1.00	EA	7% FUEL SURCHARGE	.00%	70.30	70.30

FUEL SURCHARGE IS NOT TAXABLE AND IS ADDED TO MILEAGE, PUMP AND OR DELIVERY CHARGES ONLY.

RECEIVED
 SEP 02 2004
 KCC WICHITA

EMOT

ck. 3380
 7/29/04

6223

There will be a charge of 1.5% (18% annual rate) on all past due accounts.

Copeland Acid & Cement is a subsidiary of Gressel Oil Field Service, Inc.

Gressel Oil Field Service, Inc. reserves a security interest in the goods sold until the same are paid for in full and reserve all the rights of a secured party under the Uniform Commercial Code.

REMIT TO: P.O. BOX 438 Haysville, KS 67060	NET INVOICE:	2,872.15
	SALES TAX:	25.20
	INVOICE TOTAL:	2,897.35 ✓
RECEIVED BY	COP-BUR	NET 30 DAYS



FIELD ORDER № 24937

BOX 438 • HAYSVILLE, KANSAS 67060
316-524-1225

DATE 7-19 2004

IS AUTHORIZED BY: Fritsler Trucking Inc
(NAME OF CUSTOMER)
Address Box 544 City Wess City State Ks 62560
To Treat Well As Follows: Lease Dion Well No. 1 Customer Order No. _____
Sec. Twp. Range 0.1 County Reo State Ks

CONDITIONS: As a part of the consideration hereof it is agreed that Copeland Acid Service is to service or treat at owners risk, the hereinbefore mentioned well and is not to be held liable for any damage that may accrue in connection with said service or treatment. Copeland Acid Service has made no representation, expressed or implied, and no representations have been relied on, as to what may be the results or effect of the servicing or treating said well. The consideration of said service or treatment is payable. There will be no discount allowed subsequent to such date. 6% interest will be charged after 60 days. Total charges are subject to correction by our invoicing department in accordance with latest published price schedules.

The undersigned represents himself to be duly authorized to sign this order for well owner or operator.

THIS ORDER MUST BE SIGNED BEFORE WORK IS COMMENCED
By _____ Well Owner or Operator Agent

CODE	QUANTITY	DESCRIPTION	UNIT COST	AMOUNT
	1	Pump truck squeeze	400	400
1030	51	Pump truck mileage	2.50	
	250	Sax 60/40 042 pot	6.00	
	5	sax gel	8.50	
RECEIVED				
SEP 02 2004				
KCC WICHITA				
	250	Bulk Charge	1.00	250
	51	Bulk Truck Miles 11 ton	.85	426.85
		Process License Fee on _____ Gallons		
TOTAL BILLING				

I certify that the above material has been accepted and used; that the above service was performed in a good and workmanlike manner under the direction, supervision and control of the owner, operator or his agent, whose signature appears below.

Copeland Representative Dean

Station _____ Well Owner, Operator or Agent

Remarks
KEN'S #41801

NET 30 DAYS