

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-00002-0000

LEASE NAME HINDMARSH

WELL NUMBER 2-33

660' FNL Ft. from S Section Line

660' FEL Ft. from E Section Line

SEC. 33 TWP. 29S RGE. 37W (E) or (W)

COUNTY GRANT

Date Well Completed 1/26/58

Plugging Commenced 9/13/04

Plugging Completed 9/15/04

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/03/04 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 3075' KB Bottom 2880' T.D. 5832'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2740'	2852'	13 3/8"	596'	0
				8 5/8"	2997'	696'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

9/13-15/04 P&A Operations witnessed by Jim Holland, KCC. POOH tbq. rods, subs. Cmtr to 8 5/8" csg. mix & pmp 600# cshs&12 bbl 9ppg 36cp mud&50 sx cmt plug 2740'-2590'. Load w/120 bbl mud.Cut 8 5/8" csg@696'. Circ hole w/50 bbl mud & 75 sx cmt plug 625'-525' disp w/ 17 bbl mud. pmp 40 sx cmt plug 300'-240', disp cmt w/7 bbl 36 cp mud.Cmtr load hole to 40' w/4 bbl mud & 22 sx cmt plug 40'-0'.Cut 13 3/8" csg 3'bq1, weld trash cover ID plate. RDM0.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



SUBSCRIBED AND SWORN TO before me this 20TH day of SEPTEMBER, 20 04

My Commission Expires: 5/21/2005

Notary Public