

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-067 0128-0000

LEASE NAME STUBBS, LM

WELL NUMBER 1-36

2540' FSL Ft. from S Section Line

2540' FEL Ft. from E Section Line

SEC. 36 TWP. 29S RGE. 36W (E) or (W)

COUNTY GRANT

Date Well Completed 4/11/45

Plugging Commenced 9/09/04

Plugging Completed 9/10/04

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/03/04 <sup>10</sup> <sub>9-17-04</sub> DAVID WILLIAMS (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 2950' KB Bottom 2714' T.D. 2714'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2424'	2714'	10 3/4"	547'	0
				7"	2510'	631'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

9/10/04 P&A Oper witnessed by J. Holland, KCC. POOH tbq. rods, subs. Set CIBP @ 2420'KB, spot 10'cmt @TOC 2410'. revise PBTB 2410'. Cut 10 3/4" surf csq 4' BGL, load hole w/100 bbl 9 ppg 36 cp mud, cut 7" csq@631'. Circ hole w/40 bbl 9ppg 36 cp mud, pmp 65 sx cmt plug 550'-425'+16 bbl mud. Pmp 30 sx cmt plug 300'-240'+7 bbl mud. Pmp 15 sx cmt plug 40'-surface. Weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



DEBORAH POLLOCK  
Notary Public  
SUBSCRIBED AND SWORN TO before me this 14TH day of SEPTEMBER, 20 04

My Commission Expires: 4/2/05

Notary Public