

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-20858-0000

LEASE NAME TEETER, JW

WELL NUMBER 15-23

4006' FNL Ft. from S Section Line

1450' FEL Ft. from E Section Line

SEC. 23 TWP. 30S RGE. 36W (E) or (W)

COUNTY GRANT

Date Well Completed 4-11-1989
3/20/89 *KCC BEM 9-17-04*

Plugging Commenced 9-08
9/27/04

Plugging Completed 9/08/04

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/03/04 *ob KCC BEM 9-17-04* (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2981' KB Bottom 2954' T.D. 2864'
2954 KCC BEM 9-17-04

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2468'	2710'	8 5/8"	626'	0
				5 1/2"	2954'	705'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

9/8/04 P&A Operations witnessed by J. Holland, KCC. Set CIBP @ 2400'KB, spot 20' cmt TOC@ 2380' KB. Revise PBDT 2380'KB. Load 50 bbl 9 ppg 36 cp mud, cut 5 1/2" csg @ 705' circ 40 bbl 9 ppg 36 cp mud pmped 50 sx cmt plug 650 -500' displaced cmt w/10 bbl mud. Spot 30 sx cmt plg 300'-200'+4 bbl mud. Load hole w/mud to 40', pmp 10 sx cmt plug 40'-surface. Cut off 8 5/8' csg 3' BGL, weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.


LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 14TH day of SEPTEMBER, 20 04

My Commission Expires: 3/23/06 F. Jean Tillery Notary Public



USE ONLY ONE SIDE OF EACH FORM

Form CP-4
Revised 05-88