

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-147-20,262-00-00

LEASE NAME McCamish

WELL NUMBER 1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 27 TWP. 4 RGE. 18 (X or W)

COUNTY Phillips

Date Well Completed 1/11/80

Plugging Commenced 8/14/85

Plugging Completed 8/16/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Terra Resources, Inc.

ADDRESS P.O. Box 839 Oklahoma City, OK 73101

PHONE# (405) 840-5590 OPERATORS LICENSE NO. 7368

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing-KS Depth to Top 3036 Bottom 3281 T.D. 3656

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-Kansas	Oil & Water	3055	3278	8-5/8	578	0
City				5-1/2	3388	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Hooked up to 5 1/2" casing, pumped 50 sx 60/40 Pozmix w/10% gel, 3% CaCl₂ + 2 sx hulls followed by 16 sx gel. Pumped 150 sx 60/40 Pozmix w/10% gel + 3% CaCl₂. Released 5 1/2" wiper plug and pumped 60 sx 60/40 Pozmix w/10% gel, 3% CaCl₂. Tied into 8-5/8" & 5 1/2" casing annulus. Pumped 125 sx 60/40 Pozmix w/10% gel, 3% CaCl₂ + 4 sx hulls. Stdg press 1000 psi. Tied into 5 1/2" csg,

(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Allied Cementing Co. License No. Not Known

Address Russell, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

D. J. Harris (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) D. J. Harris

(Address) P.O. Box 839, Oklahoma City, OK 73101

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 85

My Commission Expires: 2/27/89 STATE CORPORATION COMMISSION

SEP 11 1985 9-11-85 Form CP-4

Revised 08-84

CONSERVATION DIVISION
 Wichita, Kansas

pumped 75 sx 60/40 Pozmix w/10% gel, 3% CaCl₂. Cut off casing 4' below ground level and capped. Cleaned location and leveled.