

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-147-20,300 <sup>-00-86</sup> <sub>01</sub>

LEASE NAME Sutley-Quanz

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2865 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 29 TWP. 4 RGE. 18 (E) or (W)

COUNTY Phillips

Date Well Completed 3/26/81

Plugging Commenced 2/12/92

Plugging Completed 2/20/92

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 14201 East Central, Wichita, KS 67230

PHONE# (316) 733-5600 OPERATORS LICENSE NO. 5242

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing/KC Depth to Top 3074 Bottom 3124 T.D. 3330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Water	3074	3124	8 5/8	225	-0-
				4 1/2	3328	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Set plug over perforations to 3000'. Ran tbg to 1844'. Set 40 sxs plug. Perforated at 1220' & 796'. Ran tbg to 1220' circulated cmt to surface. Pulled tbg squeezed 65 sxs down csg & squeezed down surface casing with 75 sxs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Steven P. O'Neill (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 14201 East Central, Wichita, KS 67230

Subscribed and sworn to before me this 12th day of March, 19 92



[Signature]  
Notary Public

Commission Expires: \_\_\_\_\_