

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20554-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 28-11S-22W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SHAW CREEK UNIT Well #: BR 2
County: TREGO Total Vertical Depth: 4020 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 4020 w/500 sxs cmt
SURF Size: 8.625 feet: 249 w/150 sxs cmt

65
#130

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2004 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9927

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 750# hulls.
Shot tubing off at 3319'. Packer in hole at 3600'.
Casing bad. Emergency plug with rig over hole.
Dakota 830' - 945'. Anhy. 1785' - 1830'. Salt 2150' - 2250'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/17/2004 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Service RIH with tubing to 3085'.
Allied rigged up on tubing and pumped 50 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 2250' - pumped 50 sxs cement with 200# hulls mixed in.
Pulled tubing to 1800' - pumped 65 sxs cement with 250# hulls mixed in to circulate cement to surface.
Pulled tubing and tied onto 4 1/2" casing with a swedge and pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 350#.
Tied onto backside and pumped 100 sxs 60/40 pozmix with Max. P.S.I. 150#. S.I.P. 75#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3930 | 3954 | | |

Remarks: LEASE ALSO KNOWN AS BERENS-RIES #2. ALLIED CEMENTING COMPANY-TICKET #12099.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 9-23-04

NO. 2005060554

SEP 21 2004

KANSAS OIL CORP. 28-11-22W
 400 N. WOODLAWN, #2 BERENS-RIES SW NW NW
 WICHITA, KS 67208
 CONTR EMPHASIS DRLG. CO, CTY TREGO

GEOL _____ FIELD SHAW CREEK

E 2343 KB CM 5/15/79 CARD ISSUED 9/8/79 IP P 55 BOPD
 MARM 3930-3954 OA

| | |
|---|---|
| + | + |
| + | + |

API 15-195-20,554

| LOG | TOPS | DEPTH | DATUM |
|-------|------|-------|-------|
| LANS | | 3596 | -1253 |
| SWOPE | | 3794 | -1451 |
| HERT | | 3822 | -1479 |
| MARM | | 3918 | -1575 |
| ARB | | 3982 | -1639 |
| LTD | | 4404 | -2061 |
| RTD | | 4020 | -1677 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 249/150sx, 4 1/2" 4020/300sx
 DST (1) 3599-3704/30-45-60-75, REC 328'
 0, 423' WTR, 449 GCM, SIP 968-
 947#, FP 211-328/349-592#
 DST (2) 3760-3813/30-45-30-60, REC 10'
 M W/O SPTS, SIP 916-843#, FP 52-52/
 52-63#
 DST (3) 3941-3965/MIS-RUN
 DST (4) 3941-3965/45-45-60-60, REC 511'
 0, 16' W, 23' M 180' GIP, SIP 1083-
 990#, FP 74-117/127-159#
 DST (5) 3965-4013/30-30-30-30, REC
 5' DM, SIP 138-160#, FP 53-53/64-
 64#
 MICT - CO, PF (MARM) 8/3930-3934, 12/
 3938-3944, 8/3950-3954, SWB DWN, SWB
 (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS