

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00002-00-00
Spot: NENE Sec/Twnshp/Rge: 33-29S-37W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: HINDMARSH Well #: 2-33
County: GRANT Total Vertical Depth: 5832 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

PROD Size: 8.625 feet: 2997 WITH 425 SX CMT
SURF Size: 13.38 feet: 596 WITH 510 SX CMT

\$189⁵⁴

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/13/2004 11:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DAVID HIGGINS Company: PIONEER NATURAL Phone: (972) 444-9001

Proposed Plugging Method: PUMP 600# HULLS WITH 50 SX CMT. PLUG AT 625' WITH 75 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 30' WITH 22 SX CMT

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/15/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2880'. CMT RETAINER @ 2880'. 09/13/04: PUMP 600# HULLS WITH 50 SX CMT. DISPLACE TO BOTTOM. TAG TOP OF CMT @ 2461'. 09/14/04: 1ST PLUG PULL OUT OF HOLE TO 620'. LOAD HOLE & PUMP 75 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 300'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. SDON 09/15/04: 3RD PLUG PULL OUT OF HOLE TO 30'. PUMP 25 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2740	2852		

RECEIVED
SEP 24 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 696' OF 8 5/8" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 09-23-04
INV. NO. 2005060562

Form CSG