

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-00223-00-00  
Spot: NE Sec/Twnshp/Rge: 25-30S-36W  
2540 feet from N Section Line, 2540 feet from E Section Line  
Lease Name: B.D. EVANS Well #: 1-25  
County: GRANT Total Vertical Depth: 2617 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA.  
Address: 5205 N. O'CONNOR BLVD.  
IRVING, TX 75039

CIBP Size: feet: 2350 WITH 2 SX CMT  
PROD Size: 7 feet: 2410 WITH 500 SX CMT  
SURF Size: 10.75 feet: 595 WITH 400 SX CMT

# 85<sup>05</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/03/2004 11:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2350' WITH 2 SX CMT. PLUG AT 625' WITH 65 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 30' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/07/2004 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:  
PBSD 2617'. CIBP @ 2350' WITH 2 SX CMT ON TOP. LOAD CASING WITH MUD & SPOT PLUGS THROUGH CASING. 1ST PLUG AT 625' WITH 65 SX CMT. SDON. 2ND PLUG AT 300' WITH 30 SX CMT. 3RD PLUG AT 30' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2390	2617		slotted liner

RECEIVED  
SEP 24 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 827' OF 7" CASING.  
Plugged through: CSG

District: 01

RECEIVED  
SEP 15 2004  
KCC Dodge City

Signed Jim Holland PART II  
(TECHNICIAN)

INVOICED  
DATE 9-24-04  
DIV. NO. 2005060562

Form CP-2/3