

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22458-00-00
Spot: NWSESW Sec/Twnshp/Rge: 28-10S-20W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: TRIBLE Well #: 9
County: ROOKS Total Vertical Depth: 3840 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: 1601 BLAKE STREET, SUITE 500
DENVER, CO 80202

PROD Size: 5.5 feet: 3834 150 SX CMT
SURF Size: 8.625 feet: 308 185 SX CMT

124⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/20/2004 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV Tool at 1606' w/300 sxs.
PBTD 3769'. Fluid level 900'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/20/2004 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2515'.
Allied pumped 180 sxs 60/40 pozmix - 10% gel with 500# hulls - circulated cement.
PTOH. Allied squeezed with 80 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to backside - instant 600#.

Perfs:

Top	Bot	Thru	Comments
3436	3728		

RECEIVED
SEP 23 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

10.

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

9-23-04

INV. NO.

2005060556


SEP 21 2004

MONSANTO OIL COMPANY
 3030 NW EXPRESSWAY, #1203 #9 TRIBLE 28-10-20W
 OKLAHOMA CITY, OK 73112 NW SE SW

CONTR RAINS & WILLIAMSON OIL CTY ROOKS

GEOL DON RIDER FIELD TRICO

ELV 2142 KB SPD 8/10/84 CARD ISSUED 12/13/84 IP P 15 BO & 50 BWPD
2132 GL LKC 3436-3442



LOG	Tops	Depth Datum	API 15-163-22,458
TOP	3183-1041	8 5/8 " 308 / 185SX; 5 1/2 " 3834 / 150SX
HEEB	3389-1247	NO CORES OR DSTS
TOR	3409-1267	MICT - CO, PF (ARB) 3726-28, W / 4 SPF, AC 415G (28%), SWB
LANS	3429-1287	LD, NON-COMMERCIAL, PF (MARM) 3686-91, AC 250G (15%),
BKC	3642-1500	FRAC 10,000# SD & 11,000GF, SWB PT LD, NON-COMMERCIAL,
MARM	3670-1528	PF (U MARM) 3676-80, W / 2 SPF, SWB DWN, NON-COMMER-
ARB	3726-1584	CIAL, PF (LKC) 3616-21, 3598-3603, W / 2 SPF, SWB DWN,
PBTD	3769-1627	NON-COMMERCIAL, PF (LKC) 3436-42, W / 2 SPF, SWB DWN,
RTD	3840-1698	GSO, POP, P 15 BO & 50 BWPD (GR 35°), 10/22/84

NOTE: CORRECTION: 11/1/84 - ORIGINALLY FIRST REPORTED IN NE SE SW

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

11/10/84
 11/10/84
 11/10/84