

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-30213-00-00
Spot: NESW Sec/Twnshp/Rge: 9-30S-15W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: L M LEE A Well #: 3
County: BARBER Total Vertical Depth: 4771 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 4.5 feet: 4768 WITH 125 SX CMT
SURF Size: 8.625 feet: 300

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2004 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 4680' & 4 SX CMT. FREEPOINT PIPE & PULL TO 850'. PUMP 10 SX GEL & 50 SX CMT. PULL CASING TO 330' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 09/21/2004 11:30 AM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4580' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG @ 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4636	4688		

RECEIVED
SEP 24 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2720' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

[Handwritten mark]