

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20991-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 14-29S-13W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: DEROME Well #: 1
County: PRATT Total Vertical Depth: 4750 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 4739 WITH 100 SX CMT
SURF Size: 8.625 feet: 541 WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2004 9:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 4670' & DUMP 5 SX CMT ON TOP OF SAND. FREE POINT & PULL CASING TO 800'. SPOT 10 SX GEL & 50 SX CMT. PULL CASING TO 570' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 09/16/2004 2:30 PM

Witness Type: COMPLETE (100%)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4670' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 3000' WITH 25 SX CLASS "A" CMT WITH 2% GEL & 3% CC TO SHUT OFF FLOW. 2ND PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4734	4736		
4718	4720		
4714	4717		

RECEIVED
SEP 24 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3021' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form 22-2/3