

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21392-00-00
Spot: E2W2SE Sec/Twnshp/Rge: 19-33S-16W
1320 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GREGG Well #: 1-19
County: COMANCHE Total Vertical Depth: 5140 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 N.W. 112TH
OKLAHOMA CITY, OK 73162

CIBP Size: feet: 4980 WITH 2 SX CMT
COND Size: 20 feet: 45 WITH 6 YDS CMT
PROD Size: 4.5 feet: 5137 WITH 125 SX CMT
SURF Size: 13.38 feet: 315 WITH 180 SX CMT

#167⁰⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/16/2004 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS. 200# HULLS W/20/25 SX CMT BOTTOM, @ 860' 50 SX CMT
DISPLACED W/MUD @ 345' 100 SX CMT, @ 40' SX CMT, THE TOP OFF.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2004 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5096'. CIBP @ 4980' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 860' WITH 50 SX CMT. 2ND PLUG PULL TO 345' & SPOT 100 SX CMT. 3RD PLUG PULL TO 40' & SPOT 25 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5058	5078		
5043	5052		
5032	5037		

RECEIVED
SEP 24 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 3450' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

[Handwritten Signature]
(TECHNICIAN)

INVOICED

DATE 9-24-04

INV. NO. 2005060558

[Handwritten Signature]
Form C-2-2/3