



15-147-30139-00-00

69

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 - 1971
CONSERVATION DIVISION
Wichita, Kansas
7-6-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Csg. Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated.

Complete Address: P. O. Box #922, Great Bend, Kansas.

Lease Name: Sutley Well No. 7

Location: NE-SW-NW Sec. 29 Twp. 4 Rge. (E)(W) 18

County: Phillips Total Depth 3380' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 140 Sx.
3272'--4 1/2" Production casing cemented on bottom with 250 Sx. Top perforations from 3042' to 3048'.

Push plug to 3000', sand well back to 2975' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze hole with 5 sacks hulls, 20 sacks gel and 150 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent