



15-147-30086-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1965

11-22-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Fickel of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Pet Mgmt Inc.

Complete Address: 1515 Wichita Plaza, Wichita Kan.

Lease Name: Taylor Well No. 1

Location C- NW- SW Sec 28 Twp. 4 Rge. 18 (E)(W)

County Phillips Total Depth 3310 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 540ft and displaced 20 sac cement thru drill pipe, heavy mud to 140ft., set cementing plug and displace 20 sac cement, heavy mud to 40ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing to base of cellar.

Very truly yours,

Gilbert P. Lebeck
Conservation Division Agent