



15-147-20229-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

RECEIVED
CORPORATION COMMISSION
DEC 16 1980
CONSERVATION DIVISION
Wichita, Kansas
12-16-80

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Earl Lumpkins of Bensen Mineral Group has this date requested permission to plug the following described well:

Operator's Full Name: Bensen Mineral Group Inc.

Complete Address: 1726 Champa St. Suite 600 - Denver Colo. 80202

Lease Name: Quartz Well No. #1-A

Location: C-NW-NE Sec. 22 Twp. 4^S Rge. 18 (X) (W)

County: Phillips Total Depth: 3225^{EE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Lumpkins was instructed to plug the well as follows:

7" - 712^{EE} SP. cut / 350^{EE} amt -> 4 1/2" Set @ 3250' / 100^{EE} amt.

Plug Back. 3191^{EE} Perf. 3168^{EE} to 3048^{EE} No Pipe Recovery.

Ordered 250^{EE} Halliburton Light -> 8^{EE} Gel. -> 7^{EE} Shells + 4 1/2" Plug.

Pump in 4 1/2" -> 3^{EE} Shells -> 25^{EE} amt. -> 8^{EE} Gel with 2^{EE} shells.

Release Plug AND 125^{EE} amt with 4^{EE} Shells. MAX. Pressure 125^{EE} LBS.

Returned on Dec 15 - AND Pumped in 4 1/2" 10^{EE} amt. -

In Annulus pumped in 75^{EE} amt

max Pressure in Annulus 800^{EE}

Completed @ 10:20 AM Dec 15 - 1980.

Very truly yours, [Signature]
Conservation Division Agent