



15-147-20130 00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1971
CONSERVATION DIVISION
Wichita, Kansas
8-16-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ogle of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name: Grau "B" Well No. 1

Location: NE NE NW Sec. 2 Twp. 4 Rge. (E)(W) 19

County: Phillips Total Depth 3445' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Ogle was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 900' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo A. Messers
Conservation Division Agent