



15-147-20097-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

6-29-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Inc.

Complete Address: 1515 Vickers KSB&T Bldg., Wichita, Ks.

Lease Name: Gipe Well No. 2

Location: SE NE NE Sec. 1 Twp. 4 Rge. (E)(W) 19

County: Phillips Total Depth 3496' Oil Well

Gas Well Input Well SWD Well D & A XXX Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Run pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Massey
Conservation Division Agent