

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-32784-00-01
Spot: NESWSW Sec/Twnshp/Rge: 1-12S-23W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: NEWCOMER UNIT Well #: 1-6
County: TREGO Total Vertical Depth: 3787 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 5893 SADDLE CREEK TRAIL
PARKER, CO 80134

PROD Size: 4.5 feet: 3784 w/100 sxs cmt
SURF Size: 8.625 feet: 329 w/325 sxs cmt

#123⁰⁸

Well Type: EOR UIC Docket No: E16356.3 Date/Time to Plug: 09/02/2004 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JIM WACHTER Company: SHELBY RESOURCES LLC Phone: (303) 840-2183

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV Tool at 1854' w/400 sxs.
Tubing parted at 3070'.

Plugging Proposal Received By: HERB DEINES WitnessType: PARTIAL
Date/Time Plugging Completed: 09/02/2004 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Not Witnessed:
Ran tubing to 2800'.
Allied pumped 60 sxs cement with 300# hulls.
Pulled tubing to 1400' - pumped 75 sxs cement with 300# hulls - cement circulated.
Witnessed by Richard Williams-09-02-2004:
Tied onto 4 1/2" casing.
Allied pumped 90 sxs cement.
Max. P.S.I. 800#. S.I.P. 50#.
Hooked up to backside - instant 400#.
Blew hole in 8 5/8" below head.

RECEIVED
SEP 27 2004
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS LOSEE #6. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 9-28-04
INV. NO. 2005060573

SEP 21 2004

Renamed Newcomer Unit 1-6

TEXACO INC #6 LOSEE 1-12-23W
NE SW SW
Contr. LEBEN DRLG. TREGO County

E 2420KB Comm. 6/9/63 Comp. 7/10/63 IP PMP 15 BOPD+3 BW:
(LANS 3741-46)

LOG Tops	Depth	Datum
HEEB	3628	-1208
IQR	3652	-1232
LANS	3666	-1246
LTD	3787	-1367

Casing
8" 329/225 sx:
4" 3784/100 sx:

NO TESTS:

CO 3754, 20/3741-46, SWB DN, SWB
7 1/2 GO NW/3 HRS, MA 125, 750 A,
SWB PT LD + 2 1/2 BO/NW/1 HR, SWB 4
4 BO + 1 1/2 BLW/7 HRS: POP:

NEWCOMER

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

11010W