

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-30305-00-00  
Spot: SWSW Sec/Twnshp/Rge: 9-30S-15W  
660 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: L M LEE A Well #: 4  
County: BARBER Total Vertical Depth: 4771 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

PROD Size: 4.5 feet: 4576  
SURF Size: 8.625 feet: 318

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2004 2:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 4520' & 4 SX CMT. FREEPOINT PIPE & PULL TO 850'. PUMP 10 SX GEL & 50 SX CMT. PULL CASING TO 340' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/22/2004 4:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

HOLE BRIDGED OFF @ 4000' +/- . SANDED TO 3700' & 4 SX CMT. PLUGGED THROUGH CASING WHILE PULLING. 1ST PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4576	4640	OH	
3914	3930		

RECEIVED  
SEP 27 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2700' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey  
(TECHNICIAN)

Form CR-173