

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01023-00-01
Spot: SWNENE Sec/Twnshp/Rge: 6-18S-10W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: STOUT P OWWO Well #: 3
County: RICE Total Vertical Depth: 3023 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

COND Size: 15 feet: 213
PROD Size: 5.5 feet: 3014 50 SX CMT
SURF Size: 8.625 feet: 3014

98²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2004 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
SEP 21 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: PARTIAL
Date/Time Plugging Completed: 09/13/2004 12:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Set CIBP at 2950' and put 2 sacks of cement on top. Perforated at 1250', 850', and 300'. Ran tubing to 1250' and pumped 50 sacks of cement. Pulled tubing to 850' and pumped 50 sacks of cement. Pulled tubing to 300' and circulated 50 sacks of cement. Connected to 5-1/2" and pumped 60 sacks of cement at 400 lbs pressure. Connected to 15" and pumped 200 sacks of cement at 200 lbs pressure.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3014	3023		

Remarks: ALLIED CEMENT #17695

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 9.28.04
2005060572