

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20727-00-00
Spot: SESWNW Sec/Twnshp/Rge: 6-22S-9W
2970 feet from S Section Line, 990 feet from W Section Line
Lease Name: KEY Well #: 1-B
County: RENO Total Vertical Depth: 3590 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

PROD Size: 4.5 feet: 3589 125 SX CMT
SURF Size: 8.625 feet: 238 225 SX CMT

116 ⁶⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/02/2004 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
SEP 16 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/02/2004 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded off perforations to 3497' and put 4 sacks of cement on top. Cut off 4-1/2" casing at 2520'. Pulled casing to 1300' and pumped 35 sacks with 200 lbs of cotton hulls. Pulled casing to 850' and pumped 35 sacks with 200 lbs of cotton hulls. Pulled casing to 290' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3547	3552		

RECEIVED
SEP 28 2004
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE

9-28-04

INV. NO

2005060575