

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21481-00-00  
Spot: N2S2SW Sec/Twnshp/Rge: 33-31S-9W  
990 feet from S Section Line, 1460 feet from W Section Line  
Lease Name: DIRKS Well #: 1  
County: HARPER Total Vertical Depth: 4498 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N. LOGAN PO BOX 195  
ATTICA, KS 67009

SURF Size: 8.625 feet: 238 185 SX CMT

# 146<sup>19</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2004 8:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1450' & 35 sxs; 950' & 35 sxs; 288' & 35 sxs; 60' & 25 sxs; 15 sxs @ rathole & mousehole.

RECEIVED  
KCC DISTRICT #2  
SEP 10 2004  
WICHITA, KS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 05/06/2004 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

Ran open end drill pipe to 1450' and spotted 35 sacks of cement. Pulled drill pipe to 950' and spotted 35 sacks of cement. Pulled drill pipe to 288' and spotted 35 sacks of cement. Pulled drill pipe to 60' and circulated 25 sacks of cement. Circulated 15 sacks of cement in rathole and 15 sacks of cement in mousehole.

60/40 posmix with 4% gel.

RECEIVED  
SEP 28 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING

Plugged through: DP

District: 02

Signed [Signature]  
(TECHNICIAN)

INVOICED  
DATE 9-28-04  
INV. NO. 20050605-71