

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20578-00-01
Spot: NE Sec/Twnshp/Rge: 6-32S-17W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: YORK Well #: 1-A
County: COMANCHE Total Vertical Depth: 5245 feet

Operator License No.: 3869
Op Name: IMPERIAL OIL PROPERTIES, INC.
Address: 200 E FIRST ST., SUITE #413
WICHITA, KS 67202

PROD Size: 5.5 feet: 5241 WITH 150 SX CMT
SURF Size: 8.625 feet: 346 WITH 300 SX CMT

\$170⁴⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2004 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: LOAD WITH MUD. PLUG AT 1160' WITH 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2004 11:30 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5172'. CIBP @ 4950' WITH 2 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG SPOT 20 SX CMT AT 850'. 2ND PLUG PULL TO 370' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & TOP OFF WITH 15 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5158	5162		
5139	5145		
4992	4997		

RECEIVED
SEP 27 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 850' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
SEP 23 2004
KCC Dodge City

Signed

Steve Middleton

(TECHNICIAN)

INVOICED

DATE 9-28-04
TEL NO. 2005060568

Form CR-2/3