

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-19013-00-01
Spot: SESWSW Sec/Twnshp/Rge: 20-17S-9W
415 feet from S Section Line, 4148 feet from E Section Line
Lease Name: SCHROEDER OWWO Well #: 1
County: ELLSWORTH Total Vertical Depth: 3218 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 4.5 feet: 3192
SURF Size: 10.75 feet: 185

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2004 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Set CIBP above open hole and put 2 sacks of cement on top. Perforate at 1200', 900', and 250'. Run tubing to 1200' and pump 50 sacks of cement. Pull tubing to 900' and pump 50 sacks of cement. Pull tubing to 250' and circulate cement to surface.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/14/2004 1:30 PM

KCC Agent: VIRGIL CLOTHIER

RECEIVED
KCC DISTRICT #2

SEP 22 2004

WICHITA, KS

Actual Plugging Report:

Perfs:

Set CIBP at 3088' and put 2 sacks of cement on top. Perforated at 1200', 900', and 250'. Ran tubing to 1200' and pumped 50 sacks of cement. Pulled tubing to 900' and pumped 50 sacks of cement. Pulled tubing to 250' and circulated cement to surface. Topped off with approximately 40 sacks of cement on 9/15/2004.

Scout card shows 7" set at 3213'; no 7" visible or present inside 10-3/4".

60/40 posmix with 4% gel.

Allied Cement #17822
Log Tech of KS #3878

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 28 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)