

11-19

4-031875

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

KCC ap
NWNWESW

E-16,225
API number: 15-147-20,104-0001
130'W. 165'N. of
NE NW SE /4 SEC. 10, 04 S, 19 W
2475 feet from S section line
1450 feet from ~~X~~ section line
W

Operator license# 5923 Lease Flanigan well # 4

Operator: American Petroleum Co., Inc. County Phillips

Address: P.O. Box 620 Well total depth 3418 feet
Sunrise Beach, Missouri Conductor Pipe: 0 inch @ 0 feet
65079 Surface pipe 8 5/8 Inch @ 200 feet

111.09

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 19 Month: November Year: 93

Plugging proposal received from: Jim Barvais

Company: American Petroleum Phone:

Were: Order 100 sxs. 65/35 pozmix - 10% gel.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:30A.M., Day: 19, Month: November, Year: 93

Actual plugging report: 8 5/8" set @ 200' cwc. 150 sxs. 4 1/2" set @ 3418' cwc 500 sxs. 2 7/8" set @ 3107' cwc. 140 sxs. Squeezed 2 7/8" with 55 sxs. to max. P.S.I. 800#. Close in P.S.I. 800#. Tested 8 5/8" with 10 sxs. cement blend to max. P.S.I. 500#. Tested 4 1/2" annulus with no cement to 500#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
DEC 01 1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC X, NO Dakota plug:YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Carl Goodrow

INVOICED

DATE 12-3-93

INV. NO. 39316

HO. (agent)