

4-041736

15-147-20103-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-14

API Number: ~~15-147-20,130~~

SW NE SW /4 SEC. 10, 04 S, 19 W
1650 feet from S section line
3630 feet from E section line

Operator license# 5352

Lease: Flanigan Well # 3

Operator: Baird Oil Company, Inc.

County: Phillips

Address: Box 428
Logan, Kansas 67646

Well total depth 3418 111.09 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 204 feet
w/150 sxs.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: December Year 1995

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: 913-689-7456

Were: 4 1/2" casing set at 3405' w/250 sxs cement. Perf. at 3138' - 3326'. Anhy. at 1475'.
Dakota at 950'. W.L.M. at 3300'. T.O.F. at 1500'. Squeeze 4 1/2" casing at prior date.
Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All , Part [], None []

Completed: Hour: 11:45 A.M., Day: 14, Month: December, Year: 1995

Actual plugging report: Perforated casing at 1475' and 950'. Pumped in 4 1/2" casing: 25
sxs cement with 200# hulls, followed with 10 sxs gel, followed with 175 sxs cement with 200#
hulls. Max. P.S.I. 500#. S.I.P. 300#. Pressured-up 8 5/8" S.P. Max. P.S.I. 500#.

STATE CORPORATION COMMISSION
DEC 26 1995
WICHITA, KANSAS

Remarks:
Condition of casing(in hole): GOOD BAD _____ Anhy plug: YES 1465 NO _____
Bottom plug(in place): YES , CALC , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING . Elevation: _____ GL

12-26-95

I did / did not [] observe the plugging.

Dennis L. Hamel
(agent)
Form CP-2/3

INVOICED
DATE 1-8-96
INV. NO. 44426

10.