

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-195-00737-00-00
API NUMBER None drilled in 1957

LEASE NAME COOK

WELL NUMBER 13

3630 Ftt. from S Section Line

3630 Ftt. from E Section Line

SEC. 2 TWP. 11 RGE. 21 or (X)

COUNTY Trego

Date Well Completed 10-1-1957

Plugging Commenced 9-1-04

Plugging Completed 9-1-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Charter Energy, Inc.

ADDRESS P. O. Box 252, Great Bend, KS 67530

PHONE (620) 793-9090 OPERATORS LICENSE NO. 9090

Character of Well OIL

(Oil) Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-31-04 (date)
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3647 Bottom 3685 T.D. CIBP@3675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Water & oil	0	186	8 5/8	186'	0
		0	3680	5 1/2	3680	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Tubing lost in hole at 1446. Ran tubing to 1280. Mixed 50 sx w/200# hulls & 50 sx without. Circ cement to surface. Pulled tubing. Tie onto casing. Pump 150 sx w/300# hulls @ 1000# max. SI @ 500#. Check backside. Could not pump into Plugging complete.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. Unknown 99996
Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Charter Energy, Inc.

STATE OF Kansas COUNTY OF Barton, sis.

Charter Energy, Inc. (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 252, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 22nd day of September XIX 2004

Donna Moore Notary Public

My Commission Expires: 2-17-2005



DRILLERS' LOG

Company: Peel-Hardman Oil Operators

NW SE NW
Sec. 2, Twp. 11S, Rge. 21W,

Farm Name: Cook Well No. 13

County: Trego,
Kansas

Total Depth: 3685'

Comm: 9/29/57 Comp: 10/6/57

Elevation:

Contractor: Peel Brothers, Inc.

Casing: 8 5/8" @ 186' cem.
5 1/2" @ 3680' cem.

Production:

Figures below indicate bottoms of formations:

Sand	0 -	40
Sand and shale		670
Sand		900
Sand and shale		1300
Red bed and shale		1545
Anhydrite		1580
Shale and shells		1710
Shale		2135
Shale and lime		2435
Lime		2560
Lime and shale		2820
Shale		3020
Shale and lime		3395
Lime		3635
Shale and lime		3685
Total Depth		3685

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 8th day of October, 1957

My commission expires: April 27, 1960

Ruth Beak
Notary Public