

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-195-00717-00-00
API NUMBER ~~None-Drilled in 1955~~

LEASE NAME Cook

WELL NUMBER 4

3300 Ftt. from S Section Line

3630 Ftt. from E Section Line

SEC. 2 TWP. 11 RGE. 21 (N or S) (N)

COUNTY Trego

Date Well (Completed) 2-6-55 3-1955 *KCC ap*

Plugging Commenced 9-1-04

Plugging Completed 9-1-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Charter Energy, Inc.

ADDRESS PO Box 252, Great Bend, KS 67530

PHONE (620) 793-9090 OPERATORS LICENSE NO. 9090

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-31-04 (date)

by Herb Deines (KCC District Agent's Name).

Is AC-1 filed? unknown If not, is well log attached? yes

Producing Formation LKC Depth to Top 3345 Bottom 3578 T.D. CIBP @ 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Water & oil	0.	161	8 5/8	161	0
		0	3722	5 1/2	3722	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed from feet to feet each set.
Ran tubing to 2200. Mixed 125 sx cement w/250# hulls. Circ to surface. Pull tubing. Tie onto casing. Mixed 200 sx w/350# hulls. 500# max. SI @ 100#
Tie onto backside & could not pump into. Plugging complete.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. unknown 99996

Address PO Box 31, Russell, KS 67665

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Charter Energy, Inc

STATE OF Kansas COUNTY OF Barton, s.s.


SEP 24 2004
9-24-04
KCC WICHITA

Charter Energy, Inc. (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filled the the same are true and correct, so help me God.

(Signature) [Signature]
(Address) PO Box 252, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 2004, s.s.

My Commission Expires: 2-17-2005 Notary Public Donna Moore



WARRANTY LOG

Co. Peel-Hardman Oil Producers

Farm Name: Cook Well No. 4

Total Depth: 3770'

Comm: 1-29-55 Conn: 2-6-55

Contractor: Glenn W. Peel

Casing: 3 5/8" 161' con.
5 1/2" 3722.57' con.

Approx. C 1/2 SE 1/4
Sec. 2, Twp. 11S, Rge. 21E,

County: Trego,
Kansas

Elevation:

Production:

Figures below indicate bottoms of formations:

Sand	0 -	100
Shale		840
Sand and shale		1270
Shale		1520
Anhydrite		1575
Shale and shells		1575
Shale and lime		2150
Lime		2315
Lime and shale		2440
Lime		2540
Shale and lime		3080
Lime		3770
Total Depth		3770

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN to before me this 17th day of February, 1955

My commission expires: June 4, 1955

Marion M. McKelvey
Notary Public

RECEIVED
SEP 24 2004
KCC WICHITA