

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22971-00-00

LEASE NAME Noah

WELL NUMBER 9

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 2 TWP. 10S RGE. 21W (E) or (W)

COUNTY Graham

Date Well Completed 4/18/04

Plugging Commenced 4/18/04

Plugging Completed 4/18/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Elysium Energy, L.L.C.

ADDRESS 1625 Broadway, Suite 2000, Denver, CO 80202

PHONE# (303) 389-3610 OPERATORS LICENSE NO. 32754

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/18/04 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation D&A Depth to Top _____ Bottom _____ T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf.	To 212'	Size 8-5/8"	Put in 212'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Plug spotted from 3850' to 3750' w/25 sx. Plug spotted from 1800' to 1700' w/25 sx. Plug spotted from 1000' to 600' w/100 sx. Plug spotted from 275' to 175' w/40 sx. Plug spotted from 40' to surface w/10 sx. 10 sx in mouse hole, 15 sx in rate hole. All cement is 60/40 Poz w/6% gel, 1/4# CF/sx.

Name of Plugging Contractor Discovery Drilling/Allied Cementing License No. 31548

Address PO Box 763, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Elysium Energy, L.L.C.

STATE OF Colorado COUNTY OF Denver, ss.

James Annable (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) 1625 Broadway, Suite 2000, Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 24th day of September, 2004

Mendi Larue
Notary Public

Commission Expires: 8/26/06



My Commission Expires 8/26/2006

[Handwritten mark]