

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas. 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-147-20,102-00-01

LEASE NAME Clark

WELL NUMBER 3

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 10 TWP. 4S RGE. 19 (~~XX~~or(W))

COUNTY Phillips

Date Well Completed 8-70

Plugging Commenced 9/30/86

Plugging Completed 9/30/86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Inj. EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A if not, is well log attached? Submitted with plugging application

Producing Formation L/KC Depth to Top 3240' Bottom 3393' T.D. 3502'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L/KC	Water & Oil	3224'	3393'	8 5/8"	200'	-0-
				4 1/2"	3532'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped 125 sx 65/35 Pozmix w/3 sx hulls down 4 1/2" casing and 125 sx 65/35 Pozmix w/3 sx hulls down 8 5/8" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address P. O. Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.


RECEIVED
 STATE CORPORATION COMMISSION
 CONSDIV. WICHITA, KS
R. D. Roberts (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. D. Roberts

(Address) 400 N. Woodlawn, Wichita, KS 67208

OCT 1' 0 1986
10-10-86
 SUBSCRIBED AND SWORN TO before me this 8th day of October, 1986

My Commission Expires: Bonnie Brown Notary Public



DRILLERS LOG

No. 3 Clark

CASING RECORD:

8 5/8" @ 200'
w/150 sx cement

4 1/2" @ 3522'
w/500 sx cement

TOTAL DEPTH: 3595'

COMPANY:

Petroleum Management, Inc.

CONTRACTOR:

Red Tiger Drilling Company

COMMENCED:

August 13, 1970

COMPLETED:

August 19, 1970

DESCRIPTION:

SW SE SW
10-4S-19W
Phillips County,
Kansas

ELEVATION:

FORMATION

FROM

TO

REMARKS


Shale	0	870	
Sand & Shale	870	1050	
Shale	1050	1557	
Anhydrite	1557	1587	
Shale & Shells	1587	2060	
Shale & Lime	2060	3145	
Lime	3145	3595	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 20th day of August, 1970.



My Commission Expires:

10-25-72

Gloria Fawcett
Notary Public