

15-147-00035-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidav.
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Phillips County. Sec 12 Twp 4-S Rge ~~20~~ 20 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NW
Lease Owner The Palmer Oil Corporation
Lease Name Boethin Well No. 1
Office Address 415 Union National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/29/47 19
Application for plugging filed 6/28/47 19
Application for plugging approved 6/28/47 19
Plugging commenced 6/29/47 19
Plugging completed 6/29/47 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation None Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	145	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3645 - 145 Heavy Mud
145 Wooden Plug and Rock bridge
145 - 100 Cement Plug 15 sax
100 - 45 Heavy Mud
45 Wooden Plug
45 - bottom of celler cement plug 10 sax

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to The Palmer Oil Corporation
Address 415 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. P. McKee (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. P. McKee
415 Union National Bank Bldg., Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 1947
Bonnie Durrall Notary Public.

My commission expires 3/21/49



WELL LOG - BOETHIN NO. 1

Well Owner - The Palmer Oil Corporation
 Contractor - The Palmer Oil Corporation

Sec. 12-45-20W
 Location - SW SE NW
 County: Phillips County, Kansas
 Elevation: 2069
 I. P. - Dry
 Casing: 8 5/8" - 143'

Commenced: 6/18/47
 Completed: 6/29/47
 Total Depth: 3645

Cellar	0	4
Clay, sand, & shale	2	143
Shale & shells	143	441
Sand & shale	441	780
Sand & shells	780	1275
Sand	1275	1400
Sandy shale	1400	1581
Shale	1581	1583
Lime	1583	1631
Red Bed & shale	1631	1970
Shale & shells	1970	2001
Shale & lime	2001	2033
Lime	2033	2094
Shale & shells	2094	2220
Broken lime	2220	2300
Lime	2300	2351
Broken lime	2351	2645
Lime & shale	2645	3125
Lime	3125	3487
Lime & shale	3487	3520
Shale	3520	3585
Shale & lime	3585	3605
Lime	3605	3645
Total Depth		3645

FORMATION TOPS

Anhydrite	1647
Heebner	3250
Lansing	3267
Base Kansas City	3497
Conglomerate	3605
Arbuckle	3612

Drill Stem Test 3330-50; Tool open 20 minutes - recovered 180 feet muddy salt water - slight gas odor - trace oil.

THE PALMER OIL CORPORATION

7-7-47

J. P. McKee
 J. P. McKee

STATE OF KANSAS)
 COUNTY OF SEDGWICK) ss

Subscribed and sworn to before me, a Notary Public in said County and State; this 3rd day of July, 1947.

Bernice Durrall
 Notary Public

My commission expires 3/31/49.

PLUGGING
 FILE SEC 12 T 4 R 20W
 BOOK PAGE 117 LINE 23