

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 147-20109-00-01 (this well)

Operator's Full Name Petroleum Management, Inc.

Complete Address 400 North Woodlawn, Suite 201, Wichita, Kansas 67208

Lease Name Roeder Well No. 2

Location C S/2 SW SW Sec. 10 Twp. 4 Rge. (E) (W) 19

County Phillips Total Depth 3463'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 9:45 A Day 1 Month 11 Year 1978

The above well was plugged as follows:

Total Depth 3463' 8 5/8 csg set 207' cwc 150 sk.

4 1/2 csg set 3462' cw 250 sk cem. PBD 3430' with perf. (3196'-3200')

Set 14 1/2" wood plug at 3100' -poured 10' sd. -dumped 3 sk cem W/dump bailer. (3100'-3060')

Cutoff & recovered 1162' of 4 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water-

followed with 70 sk 50-50 poz 6% -displaced with 10 sk gel & water -released

cementing plug & capped with 50 sk 50-50 poz 6% & shutin. FPP 350 lbs.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 2 1978

11-2-78

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

D: 11-3-78
NO: 8471-w