

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

13-147-30141-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1966
CONSERVATION DIVISION
Wichita, Kansas
11-29-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Company Inc.

Complete Address: 211 North Broadway Wichita, Kansas

Lease Name Bach Well No. 1

Location C NW NW Sec. 10 Twp. 4 Rge. 19 (E) (W) X

County Phillips Total Depth 3335'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling Co.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 6:P Day 26 Month 11 Year 1966

The Above well was plugged as follows:

RTD 3335' 8 5/8 csg set at 216' cwc
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 25 sc
cement thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cem.
thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 10 sc cement
to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/29/66
INV. NO. 4354-W