

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20141-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
4-21-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center Wichita, Kansas 67202

Lease Name Pattom Well No. 1

Location NW SE NE Sec. 23 Twp. 4 Rge. (E) (W) 20

County Phillips Total Depth 3584'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10:30 A Day 19 Month 4 Year 1972

The above well was plugged as follows:

Tot al depth 3584' 8 5/8 csg set at 199' cwc 140 sk. Cmt. Mat. 50-50 poz cmt 6% gel.

4 1/2 csg set at 3585' cw 200 sk cmt.

4 1/2 csg FBTD 3304' & perf. (3298-3300)

Cutoff and recovered 2520' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls, -70 sk cmt -10 sk gel & water -released plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing  
Well Plugging Supervisor

DATE 4/21/72

INV. NO. 5602-W